

Scotts Valley Water District

Grace Way Well- Well Head Pedestal and Pump Installation Project

Addendum #1

7/29/2025

To be additionally included in Bid Schedule Item No.4 Well Column/Pump/Pump Motor Installation are the following components:

1. 1,080 feet of schedule 80, 1½ inch PVC Flush threaded pipe for the transducer line and sounding tube. Must be NSF 61 approved.
2. Four (4) Ductile Iron variable frequency drive rated check valves to be installed on the column piping.