



Date: 8/25/26

**2026 Glenwood Tank Site Projects:
Site Improvements (Secant Wall Installation)**

ADDENDUM NO. 4

The following clarifications and revisions are hereby incorporated in the Contract Documents, Construction Specifications and Plans for the project entitled, *"Glenwood Tank Site Project – Site Improvements (Secant Wall Installation), Scotts Valley Water District"*:

CORRECTION TO ONE QUESTION FROM REQUESTS FOR INFORMATION AND RESPONSES ISSUED IN ADDENDUM 3:

Q: Refer to Tieback Performance Test Loading Schedule in Section K.5.b. on S0.0: Please provide Tieback Design Load. Load Off Load is specified on Detail I/S3.0, but Design Load is not provided.

A: The Design Load is the same as the lock off load. 27 Kips.