

- INSTALLATION.
- O.S. AND Y. VALVES SHALL BE EQUIPPED WITH TAMPER PROOF ALARM 2. DEVICES. VALVES ARE TO BE CHAINED TOGETHER IN THE OPEN POSITION WITH A BREAK-AWAY CHAIN OR AS REQUIRED BY FIRE DISTRICT.
- ASSEMBLY TO BE PAINTED RED OR OTHER COLOR AS SPECIFIED BY 3. FIRE DISTRICT.
- DEVICE MUST BE INSTALLED SO THAT IT IS READILY ACCESSIBLE FOR TESTING AND MAINTENANCE.
- LOCATIONS MUST BE APPROVED BY SVWD PRIOR TO INSTALLATION. 5.
- 6. INSTALL TRAFFIC BOLLARDS (2 MIN) PER DETAIL 20 WHEN EDGE OF VEHICULAR TRAFFIC IS LESS THAN 36" FROM ASSEMBLY.
- 7. BRASS OR PLASTIC PLUGS SHALL BE INSTALLED ON ALL TEST PORTS.

## PLAN VIEW



## SCOTTS VALLEY WATER DISTRICT

WWW.SVWD.ORG

## DETAIL 9

STANDARD 4-INCH AND LARGER FIRE SERVICE INSTALLATION

NOT TO SCALE